



RE: Fiber Optic Construction Project

Change Order - v.1

-Extend the current 4 x 1 ¼ " conduit system from the intersection of Carpenter and Hamilton to the intersection of Hamilton and Rt. 62. Approximate footage for this build is 6072' in length.

-Provide and Place 6 - 4x4x4' manholes to existing grade (may need to be adjusted during future road construction). These will eventually be in the road, which is why manholes will need to be used.

-Provide and Place one new 144-count single mode fiber optic cable in the new section of conduit.

-Splice this section of fiber per the cities specs into the cities existing 144-count fiber.

-Final restoration to like or better conditions upon work completion.

Total Proposed Price for above work: **\$196,043.24**

This proposal includes all material and labor to complete the project. All labor rates are based on current prevailing wage rates. This proposal is also based on suitable ground conditions for construction. If such conditions are encountered, a new price may be negotiated between the contractor and the City. A purchase order is required before work can begin.

We greatly appreciate the opportunity. Please contact us with questions and concerns.

Regards,

Christopher M. Harris
President, DHB Networks
4338 Bright Rd., Dublin, OH 43016
charris@dhbnetworks.com

EXHIBIT A